

To: 1 031388
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 165-21,692-0000
50' S & 130' W of
NW SE NW, SEC. 28, T. 16 S, R. 19 W/E

TECHNICIAN'S PLUGGING REPORT 2-16
Operator License # 4767

Operator: Ritchie Exploration, Inc.
Name & Address: 125 N. Market, Ste. 1000
Wichita, KS 67202

1700 feet from N & section line
1520 feet from W & section line
Lease Name E. Littler Trust Well # 1
County Rush
Well Total Depth 3899 126.72 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 363

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420
Address P.O. Box 48848, Wichita, KS 67201-8848

Company to plug at: Hour: 10:30 p.m. Day: 15 Month: 2 Year: 19 96

Plugging proposal received from Judy
(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1297-1333'

- 1st plug at top of Arbuckle with 50 sx cement,
- 2nd plug at 1320' with 50 sx cement, 3rd plug at 690' with 60 sx cement,
- 4th plug at 360' with 40 sx cement, 5th plug at 40-0' with 10 sx cement,
- 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ No _____ X

Operations Completed: Hour: 2:30 a.m. Day: 16 Month: 2 Year: 19 96

- ACTUAL PLUGGING REPORT 1st plug at 3823' with 50 sx cement,
- 2nd plug at 1320' with 50 sx cement,
- 3rd plug at 690' with 60 sx cement,
- 4th plug at 360' with 40 sx cement,
- 5th plug at 40-0' with 10 sx cement,
- 6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If you did not observe this plugging.)

DATE 2-28-96
INV. NO. 44907
2-16

Signed Steve Durrant (TECHNICIAN)

RECEIVED COMM
KANSAS CORP
FEB 19 A 9:39

EFFECTIVE DATE: 2-7-96
DISTRICT: 1
SGA7: Yes No

State of Kansas
NOTICE OF INTENTION TO DRILL 165-21,692-0000 ALL BLANKS MUST BE FILLED

FORM MUST BE SIGNED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 2 6 96
month day year

Spot 50'S & 130'W of
ENW SE NW Sec 28 Twp 16 S Rg 19W East West

OPERATOR: License # 4767
Name: Ritchie Exploration, Inc.
Address: 125 N. Market, Suite 1000
City/State/Zip: Wichita, KS 67202
Contact Person: Lisa Thimmesch
Phone: (316) 267-4375

CONTRACTOR: License # Advise on Acc-1
Name: unknown Whitte J. Ellis

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield ... X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OUVVO ... Disposal ... X Wildcat ... Cable
... Seismic; ... # of Holes ... Other

If OUVVO: old well information as follows:
Operator: ...
Well Name: ...
Comp. Date: ... Old Total Depth: ...

Directional, Deviated or Horizontal wellbore? ... yes X ... no
If yes, true vertical depth: ...

Bottom Hole Location: ...
Exp. 8/2/96

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Judy
SPUD DATE 2-8-96 INIT. RL
LENGTH SURFACE PLANNED 396
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2 @ 363 CONDUCTOR
ANHYDRITE T-1242 B-1333 ELEVATION
TD 2311 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX Y N
1 Arbuckle Plug @ 734.6 Ft. W/ SD SX
Ing./Council @ Ft. W/ SX
0 Anhydrite Base @ 1320 Ft. W/ SD SX
1/2 Base Anyh. @ Ft. W/ SX
3 1/2, 1/2 Plug @ 690 Ft. W/ 60 SX
4 Bottom Surface @ 360 Ft. W/ 40 SX
5 40' Plug @ 40-0 Ft. W/ 10 SX
RAT HOLE CIRC/W/S SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond Δ)
TECHNICIAN SD DATE 02-13-96 Hauling
TYPE OF CEMENT 60/40 60/2
STARTING TIME 10:30 (AM/PM) DATE 2-5-96
COMPLETION TIME 2:30 (AM/PM) DATE 2-16-96
CEMENT COMPANY Allied Cement

1700 feet from South / North line of Section
1520 feet from East / West line of Section
SECTION X REGULAR IRREGULAR
(NOTE: Locate well on the Section Plat on Reverse Side)
County: Rush
Lease Name: E. Littler Trust # 1
Field Name:
Is this a Prorated/Spaced Field? ... yes X no \checkmark
Target Formation(s): Arbuckle
Nearest Lease or unit boundary: 1520
Ground Surface Elevation: 2053 2062 feet MSL
Water well within one-quarter mile: ... yes X no
Public water supply well within one mile: ... yes X no
Depth to bottom of fresh water: 180
Depth to bottom of usable water: 450 680
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 350
Length of Conductor pipe required: none
Projected Total Depth: 3900
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations: ... well ... X other

DWR Permit #: ...
Will Cores Be Taken?: ...
If yes, proposed zone: 200' Alt. II Re

RECEIVED
KANSAS CORP COMM
FEB 19 96
A 39