

To: 1 040447
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,528 - 0000
NW SW SW, SEC. 33, T. 16 S, R. 19 W/E
990 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5815
Operator: C & R Drilling
Name & Address 410 17th Street, #1140
Denver, CO 80202

Lease Name Grabbe Well # 1
County Rush 124.48
Well Total Depth 3830 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Western Kansas Drilling License Number 4083
Address P.O. Box 126, Hays, KS 67601

Company to plug at: Hour: 11 p.m. Day: 7 Month: 8 Year: 19 90

Plugging proposal received from Frank Taggert
(company name) Western Kansas Drilling (phone) 913-628-2296
Elevation 2044' GL

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1280-1308'
1st plug at 1308' with 50 sx cement, 2nd plug at 640' with 80 sx cement,
3rd plug at 270' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Stephen J. Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:15 a.m. Day: 8 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1308' with 50 sx cement,
2nd plug at 640' with 80 sx cement,
3rd plug at 270' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1990
CONSERVATION DIVISION
Wichita Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE: AUG 23 1990
INV. NO. 29005
8-8

Signed Stephen J. Pfeifer
(TECHNICIAN)

EFFECTIVE DATE: 8-5-90

State of Kansas 165-21,528-0000
NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 07/31/90
month day year

NW SW SW Sec 33 Twp 16 S, Rg 19 East West

OPERATOR: License # 5815
Name: C & R DRILLING
Address: 410 17TH ST #1140
City/State/Zip: DENVER CO 80202
Contact Person: LES OLSON
Phone: (303) 623-6144

990 feet from South Line of Section
4950 feet from East Line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License # 40B3
Name: WESTERN KANSAS DRILLING

County: RUSH
Lease Name: GRABBE Well #: #1
Field Name: UNKNOWN
Is this a Prorated Field? yes XX no
Target Formation(s): MISSISSIPPI
Nearest lease or unit boundary: 330
Ground Surface Elevation: N/A feet MSL
Domestic well within 330 feet: yes XX no
Municipal well within one mile: yes XX no
Depth to bottom of fresh water: 180
Depth to bottom of usable water: 750
Surface Pipe by Alternate: 1 XX 2
Length of Surface Pipe Planned to be set: 250
Length of Conductor pipe required: 3830
Projected Total Depth: 3830
Formation at Total Depth: MISSISSIPPI
Water Source for Drilling Operations:
well farm pond XX other
DWR Permit #: Will Cores Be Taken?: yes XX no
If yes, proposed zone: Exp. 1/31/91

Well Drilled For: Well Class: Type Equipment:
 Oil Inj Infield Mud Rotary
 Gas Storage Pool Ext. Air Rotary
 OWWO Disposal Wildcat Cable
 Seismic; # of Holes

If OWWO: old well information as follows:
Operator: Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes XX no
If yes, total depth location: Exp. 1/31/91

AFFIDAVIT

250' Alt. II Required RECEIVED
STATE CORPORATION COMMISSION

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101,
AUG 10 1990

Pusher Frank
SPUD DATE 8-1-90 INIT. CA
LENGTH SURFACE PLANNED 255'-8 5/8"
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 5/8" @ 2-52' CONDUCTOR
ANHYDRITE T- 12-80 B- 130X ELEVATION 20446.7
C 2500' 07/20/90 - 8-3-90
TD 3830 FORMATION

RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
1 Arbuckle Plug @ 200' brk. or 50' Ft. W/ 40 SX
2 Eng./Council @ 130X Ft. W/ 50 SX
3 Anhydrite Base @ 130X Ft. W/ 50 SX
4 1/2 Base Anyh. @ 640 Ft. W/ 80 SX
5 1/2, 1/2 Plug @ 270 Ft. W/ 40 SX
6 Bottom Surface @ 270 Ft. W/ 40 SX
7 40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 15 SX

WATER WELL SX (Irr. Well) Pond Hauling
TECHNICIAN SP DATE 8-3-90
TYPE OF CEMENT 60/40/60
STARTING TIME 11: (AM/PM) DATE 8-8-90
COMPLETION TIME 1:15 (AM/PM) DATE 8-8-90
CEMENT COMPANY Halleburton
CONSERVATION DIVISION
Wichita, Kansas