

1 051262

1-12

223R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,505
Irregular section
C S/2 SW SW, SEC. 30, T 16 S, R 19 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3701
Operator: Balcron Oil Company
Name & Address: P.O. Box 21017
Billings, Montana 58104

330 feet from S section line
4420 feet from E section line
Lease Name Spreier Well # 2-30
County Rush 127.73
Well Total Depth 3930 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor LOBO Drilling Company License Number 5864
Address P.O. Box 877, Great Bend, KS 67530

Company to plug at: Hour: 5 a.m. Day: 12 Month: 1 Year: 19 90

Plugging proposal received from Ervin Neighbors

(company name) LOBO Drilling Company (phone) 316-792-7476

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1329-64'

1st plug at 1360' with 50 sx cement, 2nd plug at 700' with 80 sx cement,

3rd plug at 330' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7 a.m. Day: 12 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1360' with 50 sx cement,

2nd plug at 700' with 80 sx cement,

3rd plug at 330' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1990
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(XXX/d/d both) observe this plugging.

DATE JAN 26 1990

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 27176

EFFECTIVE DATE: 12-27-89

165-21,505-0000

FORM MUST BE TYPED
FORM C-1 12/88

State of Kansas
NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

IRREGULAR SECTION
..G-22..SW..SW Sec ..30. Twp ..16. S, Rg ..19. X East

Expected Spud Date
month day year

..... 330 feet from South line of Section
..... 4420 feet from East line of Section

OPERATOR: License # 3701
Name: BALCRON OIL COMPANY
Address: P. O. Box 21017
City/State/Zip: Billings, Montana 58104
Contact Person: Alan Townsend
Phone: 406/259-7860

County: Rush
Lease Name: Spreier Well #: 2-30
Field Name: Wildcat

CONTRACTOR: License #: 5864
Name: LOBO DRILLING COMPANY

* Is this a Prorated Field? X yes ... no
Target Formation(s): ARBuckle

Well Drilled For: Well Class: Type Equipments:
... X Oil ... Inj ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OAWO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes

Nearest lease or unit boundary: 1800
Ground Surface Elevations: Unknown feet MSL
Domestic well within 330 feet: yes X .. no
Municipal well within one mile: yes X .. no
Depth to bottom of fresh water: 260'

If OAWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Depth to bottom of usable water: 660'

Directional, Deviated or Horizontal wellbore? yes X .. no
If yes, total depth locations:

Surface Pipe by Alternates: 1 X 2
Length of Surface Pipe Planned to be set: 280'


* Prorated: HAMPTON NE (ARB) OIL
Exp. 6/22/90

Spud 2/10/90
50' APPROX of 85/8

280' Alt. II Req.

1-10-90
PUSHER Ervin Neighbors
TD 3930 FORMATION
SURFACE PIPE 85' @ 300
ANHYDRITE 1329-6 ELEVATION
STARTING TIME & DATE 5:00 AM 1-12-90
COMPLETION TIME & DATE 1:00 PM 1-12-90
1st PLUG @ 47 FT. WI 47 SX
2nd PLUG @ 1360 FT. WI 50 SX
3rd PLUG @ 700 FT. WI 80 SX
4th PLUG @ 330 FT. WI 40 SX
RAT HOLE CIRCULATED WI 15 SX
MOUSE HOLE CIRCULATED WI 10 SX
WATER WELL PLUGGED WI _____ SX
CEMENT COMPANY Applied
TECHNICIAN R. L.
TYPE OF CEMENT 60/40 611

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1990
CONSERVATION DIVISION
Wichita, Kansas



- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - File Completion Form ACO-1 within 120 days of spud date;
 - File acreage attribution plat according to field prorations orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.