

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-20812-00-00  
Spot: CNWSWNW Sec/Twnshp/Rge: 30-16S-20W  
1650 feet from N Section Line, 330 feet from W Section Line  
Lease/Unit Name: STEPHENS Well Number: 1  
County: RUSH Total Vertical Depth: 4140 feet

Operator License No.: 3842

Conductor Pipe: Size \_\_\_\_\_ feet:

Operator Name: LARSON OPERATING CO. (DIV. OF

Surface Casing: Size 8.625

feet: 281

Address: 562 WEST HIGHWAY 4  
OLMITZ, KS 67564

Production: Size 4.5

feet: 4131

Liner: Size \_\_\_\_\_

feet: \_\_\_\_\_

134.55

Well Type: OIL

UIC Docket No: \_\_\_\_\_

Date/Time to Plug: 10/02/2000 2:15:00 PM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE

Company: QUALITY WELL SERVICE, INC.

Phone: (316) 727-3409

Proposed Plugging Method: AS DIRECTED BY KCC.

Plugging Proposal Received By: RICHARD LACEY

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/02/2000 3:40 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PERFS AT 4023-27, 4027-29, 4032-33, 4051-54. BRIDGED OFF AT 1230'. COULDN'T GET PAST BAD CASING. 1ST PLUG PERFORATED AT 900'. COULDN'T PULL ANY CASING. PUMPED 80 SX CMT. 2ND PLUG SHOT OFF AT 418' AND PULLED CASING TO 300'. PUMPED 50 SX CMT. 3RD PLUG PULLED CASING AND TOP OFF WITH 50 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 418' OF 4 1/2" CASING.

Plugged through: CSG

RECEIVED  
STATE CORPORATION COMMISSION

OCT 11 2000

CONSERVATION DIVISION  
Wichita, Kansas

District: 01

Signed

Michael J Maier  
(TECHNICIAN)

INVOICED

DATE

10/13/00

WEL. NO.

200-1060817

OCT 03 2000

Form CP-2/3

MP