

To: **1 120548**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-21,470-0000
C E/2 SW, SEC. 35, T. 16 S, R 20 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3701
Operator: Balcron Oil
Name & Address P.O. Box 21017
Billings, MT 59104

1320 feet from S section line
3300' feet from E section line
Lease Name Weltmer Well # 1-35
County Rush 126.42
Well Total Depth 3890 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 317

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated NEVER PRODUCED

Plugging Contractor Cheyenne Well Service License Number 6454
Address P.O. Box 384, Ness City, KS 67560

Company to plug at: Hour: 1 p.m. Day: 4 Month: 4 Year: 1991

Plugging proposal received from Morris Smith
(company name) Cheyenne Well Service (phone) 913-798-2282

were: 5 1/2" at 3888' w/150 sx cement, Perfs at 3886-88, Open hole 3888-90'
1st plug sand back to 3838' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 175 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 3 p.m. Day: 4 Month: 4 Year: 1991

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3835' and dumped 5 sx cement
on top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 175 sx cement.
Pumping pressure 0-600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied. Recovered 1550' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

DATE 4-11-91
INV. NO. 31465
4-4

Signed Duan Rankin
(TECHNICIAN)

APR 09 1991

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84