

21 *[Signature]*

To: 1 030712
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165, 20, 445-100-01

SE, SEC. 23, T 16 S, R 20 W
2310 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____
Operator: Kansas Corp. Comm.
Name & Address _____

Lease Name Hutchins Well # 1
County ^{Owmp} Rush
Well Total Depth 3895 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 7/8 feet 229

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Chase Ks.

Company to plug at: Hour: 11:30 AM Day: 3 Month: 7 Year: 19 86

Plugging proposal received from Steve Durrant

(company name) KCC (phone) _____

were: 5 1/2" @ 3894 PBTD 3786 checked with wireline

Top perfs @ 3516-19 - Bottom plug: Push plug to 3400' + 50' sand + 5sx cement with a bailer.

Shot hole in casing @ 600' & circ cement to surface.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:00 PM Day: 3 Month: 7 Year: 19 86

ACTUAL PLUGGING REPORT Ran wireline to 3786 - Push plug to 3400' with bailer. Dump 50' sand + 5sx cement on bottom.

Shot hole in casing @ 600', 1st pumped 200sx 60/40 Permox 6% gel - 3% cc. Did not circ - slight blow on annulus.

2nd pump 100sx on 5 1/2 - pressure to 800# + 300# shut in.

3rd pumped 100sx annulus @ 700# - Shut in w/ 300#

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging _____

STATE CORPORATION COMMISSION

Signed Steve Durrant (TECHNICIAN)

JUL - 8 1986

State of Kansas



JOHN CARLIN	Governor
MICHAEL LENNEN	Chairman
MARGALEE WRIGHT	Commissioner
FITH R. HENLEY	Commissioner
DITH A. McCONNELL	Executive Secretary
BRIAN J. MOLINE	General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 200 Colorado Derby Building
 202 West 1st Street
 WICHITA, KANSAS 67202-1286

June 23, 1986

9 1/2 W Liebenthal

1/2 N -

W 17th -

Fran Welsh
 Department of Administration
 Division of Purchases
 Room #165-173N
 State Office Building
 Topeka, KS 66612

RE: One abandoned well located in the NE NE SE of Sec. 23-16S-20W, Rush County, Kansas (W.D. Hutchins-OWWO#1)

Dear Fran,

This letter is to confirm our telephone conversation of June 23, 1986, granting permission to plug the above captioned well.

The well was originally drilled in August of 1972, was dry and plugged. In September of 1979, the well was re-entered by Easy Drilling Company, Hays, Kansas who are no longer in business (defunct) and later leased by L & D Oil, also no longer in business. The well was never operated by L & D Oil Company. Because of the above reasons Shari Feist, Assistant General Counsel, recommends that the Commission plug the well.

The well only has 229' of surface casing cemented in, which does not protect all of the fresh and usable water. Additionally, there are three salt water disposals within 1/2 mile of the well. At least one of the SWD wells is a shallow well (Cedar Hills). Also the well has a high fluid level of 30', making the well a serious pollution hazard. The well should be plugged as soon as possible.

Field staff estimates the cost of plugging the well at \$2,850.00.

Sincerely,

Duane Rankin
 Duane Rankin
 Field Operations Supervisor

DR/plp

cc: Barry Metz
 Arlene Clark
 Bill Bryson
 Don Ubel
~~Steve Burdick~~
 Dan Goodrow
 Shari Feist
 File-2

RECEIVED
 STATE CORPORATION COMMISSION

JUL - 8 1986

CONSERVATION DIVISION
 Wichita, Kansas