

1 030773

DEC 25 1987

API NUMBER 15- 165-21,368 - 0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

W/2 SE SW, SEC. 31, T 16 S, R 20 W/E  
660 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6569

Lease Name North Well # 1

Operator: C & C Exploration Inc.

County Rush 138.13

Name & Address 14 Circle Drive

Well Total Depth 4250 feet

Beloit, KS 67420

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 236

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 KS State Bank Bldg., Wichita, KS 67202

Company to plug at: Hour: 4:30 p.m. Day: 25 Month: 11 Year: 19 86

Plugging proposal received from Carmen Schmitt

(company name) C & C Exploration Inc. (phone) 913-738-3210

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1431'-1480'  
1st plug at 1480' with 50 sx cement, 2nd plug at 750' with 75 sx cement,  
3rd plug at 230' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:30 p.m. Day: 25 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1460' with 50 sx cement,

2nd plug at 750' with 75 sx cement,

3rd plug at 270' with 30 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION

JAN 5 1987

Remarks: Used 60/40 Pozmix 6% gel by Allied.

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE 1-6-87

Signed Steve [Signature] (TECHNICIAN)

INV. NO. 15799

11-25 JAN 08 1987

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date ... November 17, 1986

API Number 15-165-21,368-0000

OPERATOR: License # 6569
Name C. & C. Exploration Inc.
Address 14 Circle Drive
City/State/Zip Beloit KS 67420
Contact Person Carmen Schmitt
Phone 913-738-3210

W/2 SE SW Sec. 31 Twp. 16 S, Rg. 20 W
660 Ft. from South Line of Section
3630 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 660 feet
County Rush

CONTRACTOR: License #
Name Rod Tiger
City/State

Lease Name North Well # 1
Ground surface elevation 22170 feet MSL

Well Drilled For: Well Class: Type Equipment:
Oil SWD Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no

Municipal well within one mile: yes X no

Depth to bottom of fresh water 120 ft

Depth to bottom of usable water 650 600 ft

Surface pipe by Alternate: 1 X

If OWWO: old well info as follows:

Surface pipe planned to be set 220 ft

Operator

Conductor pipe required

Well Name

Projected Total Depth 4300 feet

Comp Date Old Total Depth

Formation Arbuckle

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 11-17-86 Signature of Operator or Agent Carmen Schmitt Title President

For KCC Use:

Conductor Pipe Required 200 feet; Minimum Surface Pipe Required 200 feet per Alt. 43

This Authorization Expires 5-5-87 Approved By 11-5-86

Move 11-17-86 set 8' @ 220

Rat/KCC see tab 110

W/2 SE SW Sec. 31 Twp. 16 S, Rg. 20 W

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

If 50' into Arbuckle, plug Arbuckle w. 20 SX

Table with 4 columns: Plug number, Depth (feet), Depth (sxs), and Plug description. Includes 1st through 5th plugs and Rathole/Mousehole.

PUSHER Carmen Schmitt

TD 4250 FORMATION Mica

SURFACE PIPE 236' @ 8 5/8

ANHYDRITE 143' ELEVATION 2170

STARTING TIME & DATE 4:30 pm 11/25/86

COMPLETION TIME & DATE 11-25-86

1st PLUG @ 1480 FT. W/ 60 SX

2nd PLUG @ 750 FT. W/ 75 SX

3rd PLUG @ 270 FT. W/ 30 SX

4th PLUG @ 40-0 FT. W/ 10 SX

RAT HOLE CIRCULATED W/ 15 SX

MOUSE HOLE CIRCULATED W/ SX

WATER WELL PLUGGED W/ Hand SX

CEMENT COMPANY ALLIED

TECHNICIAN P.A.J.

60/40 w/ 670 pld

1 1/2 N McInerney 34w

RECEIVED STATE CORPORATION COMMISSION JAN 5 1987 CONSERVATION DIVISION Wichita, Kansas