

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21754-00-00
Spot: N2SW Sec/Twnshp/Rge: 23-16S-20W
1915 feet from S Section Line, 1230 feet from W Section Line
Lease/Unit Name: HAMPTON PROJECT Well Number: STEPHE
County: RUSH Total Vertical Depth: 3920 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: BOX 87
SCHOENCHEN, KS 67667

Surface Casing Size: 8.625 feet: 219

\$ 127⁴⁰

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/14/2003 12:00 PM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC
Proposal Rcvd. from: BURT BEERY Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: 1ST PLUG AT 1450' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 80 SX CMT. 3RD PLUG AT 400' WITH 40 SX CMT. 4TH PLUG AT 220' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 10/14/2003 2:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:


1ST PLUG AT 1450' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 80 SX CMT. 3RD PLUG AT 400' WITH 40 SX CMT. 4TH PLUG AT 220' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED
OCT 22 2003
KCC WICHITA

Remarks: USED 60/40POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Richard M. Lacey

(TECHNICIAN)

INVOICED

DATE 10-22-03

TEL. NO. 200.406.0654

FOR [signature]