

To: 1 031080
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C S/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-16
API NUMBER 15-165-21,516-0000
SE SW, SEC. 19, T. 16 S, R. 20 (W/E)
330 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6484
Operator: Anderson Energy, Inc.
Name & Address 200 East First St., Suite 414
Wichita, KS 67202

Lease Name Fletcher Well # 1
County Rush 135.88
Well Total Depth 4181 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address 401 East Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 6:40 p.m. Day: 16 Month: 5 Year: 19 90

Plugging proposal received from Don Demel

(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1498-1532'
1st plug at 1530' with 50 sx cement, 2nd plug at 790' with 80 sx cement,
3rd plug at 300' with 40 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:30 p.m. Day: 16 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement,
2nd plug at 790' with 80 sx cement,
3rd plug at 300' with 40 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED
DATE 5-30-90
INV. NO. 28280

STATE CORP COM
MAY 21 1990

Signed Steve Durrant
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

EFFECTIVE DATE: 4/17/90

State of Kansas

165-21,516-0000

NOTICE OF INTENTION TO DRILL
Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date April 25, 1990
month day year

C S/2 SE SW Sec 19 Twp 16 S, Rg 20 East West

OPERATOR: License # 6484
Name: Anderson Energy, Inc.
Address: 200 E. First St., Suite 414
City/State/Zip: Wichita, KS 67202
Contact Person: Bill Anderson
Phone: (316) 265-7929

330 feet from South line of Section
3300 feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License # 5420
Name: White & Ellis Drilling, Inc.

County: Rush
Lease Name: Fletcher Well #: 1
Field Name: Davenport North

Is this a Prorated Field? ... yes no

Target Formation(s): Cherokee

Nearest lease or unit boundary: 330

Ground Surface Elevation: 2216 feet MSL

Domestic well within 330 feet: ... yes no

Municipal well within one mile: ... yes no

Depth to bottom of fresh water: 450

Depth to bottom of usable water: 600 750 -

Surface Pipe by Alternate: ... 1 280

Length of Surface Pipe Planned to be set: 280

Length of Conductor pipe required: N.A.

Projected Total Depth: 4150

Formation at Total Depth: Mississippi

Water Source for Drilling Operations:

... well ... farm pond ... other

DWR Permit #: _____

Will Cores Be Taken? ... yes no

If yes, proposed zone: _____

Well Drilled For: Well Class: Type Equipment:

Oil ... Inj Infield Mud Rotary
 Gas ... Storage Pool Ext. Air Rotary
 OAWO ... Disposal Wildcat Cable
 Seismic; ... # of Holes

If OAWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? ... yes no
If yes, total depth location: _____

Exp. 10/12/90

AFFIDAVIT


280' Alt. IIReq.

The undersigned hereby affirms that the drilling, completion and et. seq.

PUSHER Don Demyel
TD 481 FORMATION MIS
SURFACE PIPE 8 7/8 @ 286.0
ANHYDRITE 1498 ELEVATION 516-90
STARTING TIME & DATE 6:40 pm
COMPLETION TIME & DATE 8:30
1st PLUG @ 1530 FT. W/ 50 SX
2nd PLUG @ 790 FT. W/ 80 SX
2 1/2 Fol sand - SX
3rd PLUG @ 320 FT. W/ 40 SX
wiper plug SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ — SX
WATER WELL PLUGGED W/ pond - SX
CEMENT COMPANY Allied
TECHNICIAN SD
TYPE OF CEMENT 60/40 for 60 gal.

Spud 5-10-90
Surf 280
Haul
6 N can w/ 1/2 Co. line
Mr Crakan

Date: _____ Agent: _____



RECEIVED
MAY 21 1990

CONSERVATION DIVISION
Wichita, Kansas

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - File Completion Form ACO-1 within 120 days of spud date;
 - File acreage attribution plat according to field proration orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.