

To: 1071060  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-25  
API NUMBER 15- 165-21,609-0000  
75' S of  
W/2 SW SE, SEC. 11, T. 16 S, R. 20 W/E  
585 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 6569  
Operator: Carmen Schmitt, Inc.  
Name & Address P.O. Box 47  
Great Bend, KS 67530-0047

Lease Name Keough Well # 1  
County Rush 129.35  
Well Total Depth 3980 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 217

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Co., Inc. License Number 5929  
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 12:30 p.m. Day: 25 Month: 4 Year: 19 92

Plugging proposal received from Leonard Williamson  
(company name) Duke Drilling Co., Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1410-49'  
1st plug at Arbuckle with 40 sx cement, 2nd plug at 1450' with 50 sx cement,  
3rd plug at 700' with 80 sx cement, 4th plug at 220' with 40 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X  
Operations Completed: Hour: 2:30 p.m. Day: 25 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 1450' with 50 sx cement,  
2nd plug at 700' with 80 sx cement,  
3rd plug at 220' with 40 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

With additional description is necessary, use BACK of this form.  
(XXXX did not) observe this plugging.

**INVOICED**  
DATE 5-6-92  
INV. NO. 35172

Signed Dan Goodrow  
(TECHNICIAN)

RECEIVED  
MAY 1 1992  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS

FOR KCC USE:

FORM C-1 7/91

FORM MUST BE TYPED

FORM MUST BE SIGNED

State of Kansas

NOTICE OF INTENTION TO DRILL 165-21,609-0000 ALL BLANKS MUST BE FILLED

EFFECTIVE DATE: 4-21-92

DISTRICT #

SEAT Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Spot 75'S of East C-W/2 SW SE. Sec .11. Twp .16. S. Rg .20. X West

Expected Spud Date April 21, 1992 month day year

OPERATOR: License # 6569 Name: CARMEN SCHMITT, INC Address: P. O. Box 47 City/State/Zip: GREAT BEND, KANSAS 67530 Contact Person: Carmen Schmitt Phone: 316/793-5100

CONTRACTOR: License #: 5929 Name: DUKE DRILLING CO. INC

Well Drilled For: Well Class: Type Equipment: X Oil Enh Rec X Infield X Mud Rotary Gas Storage Pool Ext Air Rotary OVVV Disposal Wildcat Cable Seismic # of Holes Other Operator: Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no if yes, true vertical depth: Bottom Hole Location: 200' Alt. II Req.

Exp. 10/16/92

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101. et. seq.

585 feet from South /XXXXXX line of Section 2310 feet from East /XXXX line of Section IS SECTION X REGULAR IRREGULAR? (NOTE: Locate well on the Section Plat on Reverse Side) County: Rush Lease Name: Keough Well #: 1 Field Name: Keough NE Is this a Prorated/Spaced Field? yes X no Target Formation(s): Lans Arb Nearest lease or unit boundary: 330' Ground Surface Elevation: 2159' feet MSL Water well within one-quarter mile: yes X no Public water supply well within one mile: yes X no Depth to bottom of fresh water: 250 Depth to bottom of usable water: 825 Surface Pipe by Alternate: 1 X 2 Length of Surface Pipe Planned to be set: 200' Length of Conductor pipe required: N/A Projected Total Depth: 3950' Formation at Total Depth: Arbuckle Water Source for Drilling Operations: well farm pond X other DVR Permit #: Will Cores Be Taken?: yes X no If yes, proposed zone:

RECEIVED

KANSAS CORPORATION COMMISSION

APR 16 1992

609

Pusher Kenon 4-20-92 INIT. SM

LENGTH SURFACE PLANNED 200' RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 3/8" @ 217' CONDUCTOR ANHYDRITE T- 1410 B- 1449 ELEVATION

TD 3580 FORMATION Arbuckle

RAN PIPE @ DV TOOL ALT II DONE SX Y N if more than 50' Arb 40 SX Arbuckle Plug @ No Plug 3960 Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 1450 Ft. W/ 50 SX 1/2 Base Anyh. @ 700 Ft. W/ 80 SX 1/2, 1/2 Plug @ Ft. W/ SX Bottom Surface @ 220 Ft. W/ 40 SX 4 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN DG DATE 4-24-92

TYPE OF CEMENT 60/40 6% STATE OF KANSAS CONSERVATION DIVISION DATE 4-25-92 COMPLETION TIME 2:30 (AM/PM) DATE 4-25-92 RECEIVED CEMENT COMMISSION