

1090365

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,157 -0000

NE SW NW, SEC. 2, T 16 S, R 20 W/R

3630 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9446

Lease Name Wassinger Well # 1

Operator: N. F. Producers, Inc.

County Rush 122.27

Name & Address 5151 W. First Avenue

Well Total Depth 3762 feet

Denver, CO 80214

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 226

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Ness County Well Service License Number 7527

Address Box J, Ness City, KS 67560

Company to plug at: Hour: 2:30 pm Day: 27 Month: June Year: 19 85

Plugging proposal received from Tom Skinner

(company name) N. F. Producers (phone) 303-934-2464

were: 4 1/2" at 3760' PBD 3760' Perfs at 3432-34; 3440-42; 3476-78'

1st plug sand back to 3380' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Robert B. Tarbutton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4:00 pm Day: 27 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3380' and dumped 4 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10

sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JUL 09 1985

Maximum pressure 600 psi and shut in 300 psi

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan. Recovered 2050' 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 7-12-85

Signed Robert B. Tarbutton (TECHNICIAN)

INV. NO. 8909

6-27 JUL 31 1985