

1090364

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,174-000

SE NW NE, SEC. 2, T 16 S, R 20 W/E

4290 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9446

Lease Name Ree Well # 1

Operator: N.F. Producers, Inc.

County Rush 123.60

Name & Address 5151 W. First Avenue

Well Total Depth 3803 feet

Denver, CO 80214

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 248

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Ness County Well Service License Number 7527

Address Box J, Ness City, KS 67560

Company to plug at: Hour: 5:15 pm Day: 27 Month: June Year: 19 85

Plugging proposal received from Tom Skinner

(company name) N.F. Producers (phone) 303-934-2464

were: 4 1/2" at 3800' PBD 3800' Perfs at 3764-68.

1st plug sand back to 3700' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 150 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Robert B. Tarbutton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 6:00 pm Day: 27 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3700' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 10 sx gel, 100 sx cement, 1 sack hulls and 75 sx cement.

Ran wireline to check top of cement. Top of cement at 60 feet. Cemented from 60 feet to surface.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 800 psi and shut in 1000 psi

Remarks: Recovered 750' 4 1/2" casing cemented by BJ-Titan Used 60/40 Pozmix 6% gel

(If additional description is necessary, use BACK of this form.)

INVOLCED

DATE 7-12-85

Signed Robert B. Tarbutton (TECHNICIAN)

INV. NO. 8908

6-27