

1 020201

1-6

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21.455 - 0000
SE SE NW, SEC. 26, T 16 S, R 20 W EX

2970 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3922

Lease Name Elmore Well # 1-26

Operator: Intrepid Production Company

County Rush 128.70

Name:

Address 718 17th Street, Suite 1810

Well Total Depth 3960 feet

Denver, CO 80202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 279

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 1 p.m. Day: 6 Month: 1 Year: 19 89

Plugging proposal received from Wilmer Dreiling

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

Elevation 2124'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1355-92'

1st plug at Arbuckle with 50 sx cement, 2nd plug at 1392' with 50 sx cement,

3rd plug at 790' with 80 sx cement, 4th plug at 290' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9 p.m. Day: 6 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 3885-3960' with 50 sx cement,

2nd plug at 1392' with 50 sx cement,

3rd plug at 790' with 80 sx cement,

4th plug at 290' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 12 1989

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

INVOICED (If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

DATE 1-17-89

INV. NO. 23656

Signed Glenn Barlow
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date..... 12 29 88
month day year

OPERATOR: License # 3922
Name Intrepid Production Company
Address 718 17th Street, Suite 1810
City/State/Zip Denver, CO 80202
Contact Person Charlie Sturdavant
Phone (303) 534-2100

API Number 15- 165 - 21,455-0000

SE SE NW Sec. 26 Twp. 16 S, Rg. 20 ☒ East
2970 Ft. from South Line of Section
2970 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 2310 feet
County Rush

Lease Name Elmore Well # 1-26

Ground surface elevation N/A feet MSL

Domestic well within 330 feet: — yes ☒ no

Municipal well within one mile: — yes ☒ no

Depth to bottom of fresh water 400

Depth to bottom of usable water 625 700

Surface pipe by Alternate: 1 2 ☒

Surface pipe planned to be set 260

Conductor pipe required

Projected Total Depth None feet

Formation Arbuckle

CONTRACTOR: License # 5422 316-262-1841
Name Abercrombie Drilling, Inc. 801 W. 10th
City/State Wichita, KS 67202

Well Drilled For: Well Class: Type Equipment:
☒ Oil ☐ Storage ☐ Infield ☒ Mud Rotary
☐ Gas ☐ Inj ☐ Pool Ext. ☐ Air Rotary
☐ OWWO ☒ Expl ☐ Wildcat ☐ Cable

If OWWO: old well info as follows:

Operator

Well Name N/A

Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 12-28-88 Signature of Operator or Agent Title Vice President

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200' feet per Alt. ☒ 2

This Authorization Expires 6-28-89 Approved By LKM 12-28-88

EFFECTIVE DATE: 1-2-89

RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1989

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep.	Base-Anhydrite	or formation with	50 SX	feet of	60-40 pos, 6% gel
2nd plug @ ft. deep.	Chey. Dakota	or formation with	80 SX	feet of	60-40 pos, 6% gel
3rd plug @ ft. deep.	330'	or formation with	50 SX	feet of	60-40 pos, 6% gel
4th plug @ ft. deep.	40'	or formation with	10 SX	feet of	60-40 pos, 6% gel
5th plug @ ft. deep.		or formation with		feet of	

(2) Rathole to surface minus 5 feet 15 SX. 60-40 pos, 6% gel

(b) Mousehole to surface minus 5 feet

PUSHER W. Drilling

TD 3960' FORMATION Arb.

SURFACE PIPE 8 5/8" @ 279'

ANHYDRITE 1355' ELEVATION 2124'

STARTING TIME & DATE 1-6-89 1:00 PM

COMPLETION TIME & DATE 1-6-89 9:00 PM

3885-3960'

1st PLUG @ 1355' FT. W/ 50 SX

2nd PLUG @ 1392' FT. W/ 50 SX

3rd PLUG @ 790' FT. W/ 90 SX

4th PLUG @ 290' FT. W/ 40 SX

5th PLUG @ 40' FT. W/ 15 SX

RAT HOLE CIRCULATED W/ 15 SX

MOUSE HOLE CIRCULATED W/ 15 SX

WATER WELL PLUGGED W/ 15 SX

CEMENT COMPANY Allied

TECHNICIAN D.G.

60/40 670

Allen Barlow