

To: 1 120975 9-28  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,559-0000  
N/2 SE NW SEC. 26, T 16 S, R 20 W/E  
3630 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4011  
Operator: Ummels Tank Service  
Name & Address: Box 37  
Brownell, KS 67521

Lease Name Elmore Well # A-1  
County Rush  
Well Total Depth 3945 128.21 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Ummels Tank Service License Number 4011  
Address Box 37, Brownell, KS 67521

Company to plug at: Hour: 1:30 p.m. Day: 28 Month: 9 Year: 19 94

Plugging proposal received from Dean Ummel  
(company name) Ummels Tank Service (phone) 913-481-2316

were: 5 1/2" at 3944' w/150 sx cement, PBD 3922', Perfs at 3868-78', DV @ 1260' w/275 sx cement  
1st plug pump in 5 1/2" casing with 200 lbs. hulls, 40 sx cement, 20 sx gel, and 100 sx cement.  
Check 8 5/8" X 5 1/2" annulus.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 p.m. Day: 28 Month: 9 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped into 5 1/2" casing with 200 lbs. hulls, 50 sx cement,  
20 sx gel, 50 lbs. hulls, and 110 sx cement. Pumping pressure 0-1500 psi and shut in 1000 psi.  
2nd plug pumped in 8 5/8" X 5 1/2" annulus with 15 sx cement. Shut in pressure 500 psi.

Remarks: Used 65/35 Pozmix 6% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

~~Mid / XXXXXX~~ observe this plugging.

INVOICED  
DATE 10-10-94  
INV. NO. 41392  
9-28

Signed Richard Lacey  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 04 1994  
CONSERVATION DIVISION  
WICHITA, KANSAS