

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-145-20,982 ⁰⁰⁰⁰⁰ R

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Hupfer Oil Co.

Complete Address 2309 Walnut Hays Ms. 67601

Lease Name Spricer Well No. 1

Location NE-SE-NW Sec. 1 Twp. 21 Rge. 16 (East) (West)

County Pawnee Total Depth 3810

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor H-30 Oil Co.

Address 251 N. Water Wichita Ms. 67202 License No. _____

Operation Completed: Hour: 9:45 AM Day: 22 Month: 7 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" S.P. to 982' w/ 450 sx 60/40 Pozmix 2% gal-3% cc + cur.

Order: 125 sx 50/50 Pozmix 4% gal-3% cc.

1st plug @ 990' w/ 60 sx

2nd plug @ 420' w/ 40 sx

3rd solid bridge
Hulls-plug @ 40' → cm to 0' w/ 10 sx

5th Rat hole w/ 10 sx

Water well w/ 5 sx

Amount of Surface Casing: 982'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Steve Summit
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
AUG 02 1982
8-2-82
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED
DATE 8-9-82
INV. NO. 802-W