

15-165-28113-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3-4-68
MAR 4 - 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 105 Fourth National Building Wichita, Kansas

Lease Name Schneider "I" Well No. 1

Location SE SW SW Sec. 29 Twp. 16 Rge. 19 (E) (W) X

County Rush Total Depth 3928'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Russ Casing Plg.

Address: Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 3 P Day 28 Month 2 Year 1968

The Above well was plugged as follows:

Total Depth 3928' 8 5/8 csg set at 240' cwc 165 sc. Cem. Mat. 140 sc 6% poz cement.
5 1/2 csg set at 3923' -cw-150-sc-cement. 30 sc gel and 6 sc hulls.

5 1/2 PBD 3465' with top perf. at 3445'

Filled with sand to 3420' and dumped 5 sc cement with dump bailer.

Recov. 3033' of 5 1/2 csg.

Squeezed thru 8 5/8 csg with 30 sc gel W/6 sc hulls, plug and 140 sc 6% pozmix cement.

Circ. pres. 350 lbs. Shutin pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/4/68
INV. NO. 7356-U

Signed: Leo Z. Massey
Well Plugging Supervisor