

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 7 1972  
8-7-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Alpar Resources, Inc.

Complete Address Box 906 Perryton, Texas

Lease Name Schneider Well No. 1

Location NW SW SW Sec. 29 Twp. 16 Rge. (E) (W) 19

County Rush Total Depth 3850'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.     

Operation Completed: Hour 7:30 P Day 2 Month 8 Year 1972

The above well was plugged as follows:

RTD 3850' 8 5/8 csg set at 246' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Murray  
Well Plugging Supervisor

DATE 8-7-72

INV. NO. 6132-40