

15-135-19048-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 10 1972

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Mobil Oil Corporation

Complete Address Box 1934 Oklahoma City, Oklahoma 73101

Lease Name Herbert Moore Well No. 1

Location C NW NE Sec. 7 Twp. 20 Rge. (E) (W) 21

County Ness Total Depth 4381'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Glenn & Smith Pipe Pulling

Address Box 156 Ellinwood, Kansas 67526 License No. 396

Operation Completed: Hour 11 A Day 8 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 4381' 8 5/8 csg set at 323' cwc

5 1/2 csg set at 4379' cw 75 sk cmt.

Filled 5 1/2 csg W/sd (4365-4381) Dumped 5 sk cmt W/dump bailer. (4330-4365)

Cutoff and recovered 2500' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel W/2 1/2 sk hulls <sup>released 8 5/8 plug</sup> -80 sk cmt -10 bbl water

and 20 sk cmt W/1/2 sk hulls. PP 250 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 4-11-72

INV. NO. 5520-U