

15-135-20371-0008

Form CP-3  
Rev. 6-4-68

KANSAS

*20*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 12 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Mull Drilling Company, Inc.

Complete Address 1625 Wichita, Plaza Bldg., Wichita, Kansas

Lease Name Wancura Well No. 1

Location C SE SW Sec. 31 Twp. 17 Rge. (E) (W) 26

County Ness Total Depth 4546

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Rains & Williamson

Address Wichita, Kansas License No.       

Operation Completed: Hour 8:30 A Day 7 Month 10 Year 1970

The above well was plugged as follows:

RTD 4546' 8 5/8 csg set at 321' cwc Cmt. Mat. 100 sk 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 300' set-cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey  
Well Plugging Supervisor

DATE 10-12-70

INV. NO. 2670-W