

15-135-20306-0000

Form CP-3
Rev. 6-4-68

KANSAS

af
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bankoff Oil Company

Complete Address Drawer 2497 Tulsa, Oklahoma

Lease Name Norton Well No. 1

Location App. C SW NW Sec. 36 Twp. 17 Rge. (E) (W) 26

County Ness Total Depth 4470

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Leben Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 12N Day 19 Month 12 Year 1969

The above well was plugged as follows:

RTD 4470' 8 5/8 csg set at 292' cwc Cmt. Mat. 50-50 poz cmt 6%.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced

70 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and displaced

20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and

10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 12-22-69

INV. NO. 1097-W