

15-135-21060-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

JUN 10 1975
06-10-75
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address 705 4th Natl. Bank Bldg., Wichita, Kansas

Lease Name Norton "P" Well No. 1

Location NW NW Sec. 36 Twp. 17 Rge. (E) (W) 26

County Ness Total Depth 4420'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 3:30 A Day 7 Month 6 Year 1975

The above well was plugged as follows:

RTD 4420' 8 5/8 csg set 216' cwc 150 sx. Chg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 6/13/75
INV. NO. 1479-W