

15-135-19189-0000

Form CP-3
Rev. 6-26-62

14
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 14 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Kimberlin Exploration Co

Complete Address: 201 University Blvd Denver, Colo.

Lease Name Norton Well No. 1

Location CSW NE Sec. 36 Twp. 17 Rge. (E) (W) 26

County Ness Total Depth 4408

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kans License No. 436

Operation Completed: Hour 10AM Day 6 Month 5 Year 65

The Above well was plugged as follows:

8 5/8" 219' circulated with cement - 4 1/2" 4400' with 175 sax cement
Sand to 3390' set 4 sax cement with dump bailer - pulled 2683' 4 1/2" to
700' circulated hole with heavy gel mud through 4 1/2" at 700' (40 sax Gel)
displaced 20 sax cement through 4 1/2" at 700', heavy mud to 200', displaced
20 sax cement through 4 1/2" at 200', heavy mud to 35', cement 35' to 0'

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Robert Perry*
Well Plugging Supervisor

DATE 5/14/65
INV. NO. 1160-W