

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Aspen Drilling Company

Complete Address: P. O. Box 783 Great Bend, Kansas

Lease Name Harkness Well No. 1

Location NE NW NE SW Sec. 34 Twp. 17 Rge. 26 (E) (W) X

County Ness Total Depth 4480'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 11:15 A Day 24 Month 4 Year 1967

The Above well was plugged as follows:

RTD 4480' 8 5/8 csg set at 332' cwc 175 sc.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 25 sc cem.

thru drill pipe. Heavy mud to 320' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/24/67

INV. NO. 5114-4

Signed: Ron J. Massey
Well Plugging Supervisor