



SP

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 18 1967
 9-18-67
 CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Sept 11, 1967.

Dear Sir:

Mr. Kenneth Smith of Flint Engine & Constr. Co. has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: W. F. Braden & Sons

Complete Address: 215 South Star Eldorado, Kansas.

Lease Name: Stephenson Well No. #1

Location: W/2 Sw Sec. 11 Twp. 26 Rge. 4E (E) (W) E

County Butler Total Depth 1980' Oil Well Abd.

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

No surface pipe. 1980' of 5 1/2" long string. Top perforation
at 1968' Sand to 1960' & 5 sacks cement. Mud to 200'. 15'
rock bridge & 5 yards ready-mix cement. Mud to 30' & 1 yard
ready-mix to base of cellar. 1820' of 5 1/2" pipe pulled.
150' of 7" pipe pulled.

Very truly yours,

Herman Justus
 Conservation Division Agent