

State of Kansas



15-083-10215-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 10 1966

CONSERVATION DIVISION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Pulley of Mull Drlg. Co., Inc. has this

date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Inc.

Complete Address: 1625 Wichita plaza, Wichita, Kansas

Lease Name: Scothorn Well No. 1,

Location: C NE NE Sec. 22 Twp. 22 Rge. 23 ~~(E)~~ (W)

County Hodgeman Total Depth 4571' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pulley was instructed to plug the well as follows:

8 5/8" to 382' circulated w/ cement. 4 1/2" to 4568' cemented.

No Perforations Plug bottom w/ sand & 5 sacks cement.

Top of cement 4440' Mud 4440' to 400'

Spotted 25 sacks cement 400' to 325' Mud 325' to 35'

Plug, Halls & 10 sacks cement 35' to 0'

Very truly yours,

Edward J. Eves
Conservation Division Agent