

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202.

RECEIVED
 STATE CORPORATION COMMISSION

NOV 6 1968

CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Rode of Rains & Williamson has this date requested permission to plug the following described well:

Mr. Rode guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Co., Inc.

Complete Address: 1425 Wichita Plaza Wichita, Ks.

Lease Name: Beltz Well No. 1

Location: C SE NW Sec. 34 Twp. 20 Rge. 21 (E)(W)XX

County: Ness Total Depth 4444 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rodie was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace
70 sc cement thru drill pipe. Heavy mud to 270' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Geo. F. Moseley
 Conservation Division Agent