

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sharpe of Barnett Oil C, has this
date requested permission to plug the following described well:

Mr. Sharpe guarantees payment of the plugging fee.

Operator's full Name: Barnett Oil Company

Complete Address: 411 1st Nat'l Bank Bldg. Wichita, Kansas

Lease Name: Rein Well No. 1

Location: SE NW Sec. 4 Twp. 20 Rge. 21 (E)(W) X

County Ness Total Depth 4543 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sharpe was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 680° and displace
100 sc cement thru drill pipe. Heavy mud to 400° set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40° set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Law F. Massey
Conservation Division Agent