



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 22 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bishop of Leben Drlg. has this

date requested permission to plug the following described well:

Mr. Bishop guarantees payment of the plugging fee.

Operator's full Name: Bankoff Oil Co.

Complete Address: Drawer 2497 Tulsa, Okla.

Lease Name: Norton Well No. 1

Location: C SW NW Sec 36 Twp. 17 Rge. (E)(W) 26

County: Ness Total Depth 4470 Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Bishop was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace  
70 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. F. Massey  
Conservation Division Agent