

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23816-00-00  
Spot: NESWNESE Sec/Twnshp/Rge: 28-13S-15W  
1950 feet from S Section Line, 700 feet from E Section Line  
Lease Name: ROHLEDER Well #: 2  
County: RUSSELL Total Vertical Depth: 3420 feet

Operator License No.: 34259  
Op Name: JAG OPERATIONS, INC.  
Address: 710 S. FRONT PO BOX 628  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	212		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/20/2012 12:00 AM  
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.  
Proposal Rcvd. from: BILL SANDERS Company: SOUTHWIND DRILLING, INC. Phone: (620) 617-0706

Proposed Plugging Method: Ordered 185 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE  
Date/Time Plugging Completed: 08/20/2012 3:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @1000 w/25 sx  
2nd plug @500 w/80 sx  
3rd plug @275 w/40 sx  
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

RECEIVED  
AUG 27 2012  
KCC WICHITA

Remarks: QUALITY WELL SERVICE

Plugged through: DP

District: 04

Signed [Signature]  
9/10/12 (TECHNICIAN)

AUG 21 2012