

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22179-00-00

Spot: NWSENNWNE

Sec/Twnshp/Rge: 26-26S-14W

4600 feet from S Section Line, 1967 feet from E Section Line

Lease Name: MCMANNIS

Well #: 1

County: PRATT

Total Vertical Depth: 4550 feet

Operator License No.: 8061

Op Name: OIL PRODUCERS INC. OF KANSAS

Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3829		WITH 2 SX CMT
CIBP		4220		WITH 2 SX CMT
PROD	4.5	4548	2330	WITH 175 SX CMT
SURF	8.625	337		WITH 205 SX CMT

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/14/2012 11:00 AM

Plug Co. License No.: 34082

Plug Co. Name: ALLIANCE WELL SERVICE INC.

Proposal Rcvd. from: BARRY WALTERS

Company: ALLIANCE WELL SERVICE INC.

Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP'S @ 4229' & 3829' W/2SX CMT ON TOP OF EACH CIBP. PLUG AT 900' WIWHT 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 10 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 08/14/2012 12:35 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP'S @ 4220' & 3829'. PUT 2 SX CMT ON TOP OF EACH CIBP THROUGH DUMP BAILER. 1ST PLUG AT 904' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 374' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4279	4293		
4066	4068		
4034	4036		
4002	4006		
3943	3946		
3879	4068		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

AUG 20 2012

KCC DODGE CITY

Signed

Stephen J Pfeifer
(TECHNICIAN)
9/10/12

RECEIVED
AUG 27 2012
KCC WICHITA