

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21564-00-00
Spot: W2NENWSE Sec/Twnshp/Rge: 4-27S-16W
2313 feet from S Section Line, 1759 feet from E Section Line
Lease Name: SUTTON Well #: 1-4
County: KIOWA Total Vertical Depth: 4618 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4470		WITH 2 SX CMT
PROD	4.5	4617	3005	WITH 150 SX CMT
SURF	8.625	450		WITH 275 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/16/2012 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4470' WITH 2 SX CMT. PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 60' WITH 15 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/16/2012 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4470' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 1125' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 470' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4582	4590		
4520	4550		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Stephen J. Pape
(TECHNICIAN)

RECEIVED

AUG 20 2012

KCC DODGE CITY

RECEIVED
AUG 27 2012
KCC WICHITA

Rowe