

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26352-00-00
Spot: SWSNWNW Sec/Twnshp/Rge: 15-12S-17W
1015 feet from N Section Line, 675 feet from W Section Line
Lease Name: HERMAN Well #: 1-15
County: ELLIS Total Vertical Depth: 3780 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1116		400 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/08/2012 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: KURT STRUBE Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 245 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE
Date/Time Plugging Completed: 08/08/2012 1:15 PM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st plug @3758 w/25 sx
2nd plug @1380 w/25 sx
3rd plug @1160 w/40 sx
4th plug @800 w/100 sx
5th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

District: 04

Signed Ed Schumacher
9/10/12 (TECHNICIAN) CM

AUG 22 2012

RECEIVED
AUG 27 2012
KCC WICHITA