

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21942-00-00
Spot: NESESWNE Sec/Twnshp/Rge: 8-33S-42W
2250 feet from N Section Line, 1450 feet from E Section Line
Lease Name: HENTSCHEL C Well #: 3
County: MORTON Total Vertical Depth: 3935 feet

Operator License No.: 5447

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1419		WITH 485 SX CMT

Op Name: OXY USA INC.

Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

Well Type: DH

UIC Docket No:

Date/Time to Plug: 08/23/2012 12:00 PM

Plug Co. License No.: 34660

Plug Co. Name: AZTEC WELL SERVICING CO.

Proposal Rcvd. from: JEFF GILL

Company: AZTEC WELL SERVICING CO.

Phone: (505) 334-6194

Proposed
Plugging
Method:

1ST PLUG AT 1519' WITH 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. NO RAT HOLE. 4TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI

WitnessType: NONE

Date/Time Plugging Completed: 08/23/2012 12:00 PM

KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

Perfs:

1ST PLUG AT 1519' WITH 100 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. NO RAT HOLE. 4TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: DP

District: 01

Signed

Daniel Bernasconi

9/10/12

(TECHNICIAN)

RECEIVED

AUG 28 2012

KCC DODGE CITY

RECEIVED
AUG 30 2012
KCC WICHITA

AWY