

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22694-00-00
Spot: NENESWNE Sec/Twnshp/Rge: 31-31S-12W
1496 feet from N Section Line, 1417 feet from E Section Line
Lease Name: HALL Well #: 2
County: BARBER Total Vertical Depth: 4511 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4457		WITH 2 SX CMT
PROD	4.5	4505	3144	WITH 150 SX CMT
SURF	8.625	349		WITH 230 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/20/2012 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4455' WITH 2 SX CMT. PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 15 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/21/2012 10:11 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4457' WITH 2 SX CMT ON TOP WITH DUMP BAILER. 1ST PLUG AT 671' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 365' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4505	4510		

RECEIVED
AUG 30 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Richard M. Lacey
9/10/12 (TECHNICIAN)

RECEIVED
AUG 28 2012
KCC DODGE CITY

BWY