

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-20590-00-00  
Spot: E2NENW Sec/Twnshp/Rge: 16-23S-16W  
761 feet from N Section Line, 2419 feet from W Section Line  
Lease Name: ZOOK TOWNSITE Well #: 1  
County: PAWNEE Total Vertical Depth: 4260 feet

Operator License No.: 5141  
Op Name: ZENITH DRILLING CORPORATION  
Address: PO BOX 780428  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4259	1517	WITH 125 SX CMT
SURF	8.625	254		WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/22/2012 11:00 AM  
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC  
Proposal Rcvd. from: ALLEN WALKER Company: ZENITH DRILLING Phone: (316) 755-3523

Proposed Plugging Method: RUN TBG TO 4100' & PUMP 30 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/22/2012 2:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

RAN TBG TO 4100' & PUMP 30 SX CMT. 1ST PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 20 SX CMT.

RECEIVED  
AUG 30 2012  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Richard M. Lacey  
9/10/12 (TECHNICIAN)

RECEIVED

AUG 28 2012

KCC DODGE CITY