

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21917-00-00
Spot: NWNESE Sec/Twnshp/Rge: 32-19S-10W
2038 feet from S Section Line, 779 feet from E Section Line
Lease Name: RINGWALD A Well #: 3
County: RICE Total Vertical Depth: 3280 feet

Operator License No.: 30380
Op Name: HUPFER OPERATING, INC.
Address: PO BOX 3912
SHAWNEE, KS 66203

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3068		
PROD	5.5	3279	1150	400 SX
SURF	8.625	262		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/21/2012 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKES TESTING & SALVAGE, INC. Phone: (620) 562-0895

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 08/21/2012 9:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 2860' AND CAP WITH 5 SX'S CEMENT. CUT CASING AT 1150' AND PUMP 35 SX'S CEMENT. PULL CASING TO 900' AND PUMP 35 SX'S CEMENT. PULL CASING TO 325' AND CIRCULATE CEMENT TO SURFACE. PULL CASING ON OUT AND TOP OFF. USED 190 SX'S.

Perfs:

Top	Bot	Thru	Comments
2916	2922	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 04 2012

CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET C-39989. DENIED TA DUE TO HFLD.

Plugged through: CSG

District: 02

Signed Virgil Clothier
9/10/12 (TECHNICIAN)

JK