

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-40219-00-00
Spot: NWSWNWSW Sec/Twnshp/Rge: 31-24S-4E
1938 feet from S Section Line, 5029 feet from E Section Line
Lease Name: PURE Well #: 2
County: BUTLER Total Vertical Depth: 2681 feet

Operator License No.: 5387
Op Name: THE BUCKEYE CORPORATION DBA A
Address: PO BOX 1020
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2443		100 SX
SURF	20	38		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/26/2012 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: STEVEN W. KILE Company: AZTEC OIL CO Phone: (316) 321-3800

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 07/27/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2600', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 30 SXS CLASS A 3% CC AND DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2225. TESTED CASING @ 100#, HELD OK. 7-27-2012, RIH ON WIRELINE, SHOT SQUEEZE HOLES (4-HOLES) 250'-251'. SWEDGED INTO 7" CASING, CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 230 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 7-27-2012. CONSOLIDATED CEMENT TICKET #'S 34815, & 34816.

Perfs:

Top	Bot	Thru	Comments
2443	2681	OH	

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 04 2012
CONSERVATION DIVISION
WICHITA, KS

Remarks: LEFT 7" PACKER IN HOLE @ 2,643'

Plugged through: TBG

District: 02

Signed [Signature] DISTRICT SUPERVISOR
(TECHNICIAN)