

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00764-00-00
Spot: SENWNW Sec/Twnshp/Rge: 3-30S-8W
4290 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BERTHOLF B Well #: 1-3
County: KINGMAN Total Vertical Depth: 4235 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4229	2024	150 SX
SURF	8.625	407		250 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/20/2012 8:00 AM

Plug Co. License No.: 8273 Plug Co. Name: EXCELL SERVICES, LLC

Proposal Rcvd. from: KEITH SHEHAN Company: CHESAPEAKE Phone: _____

Proposed Plugging Method: CIBP 4080, 35 SKS 1200', 35 SKS 750, CIRC CMT 450-0

Plugging Proposal Received By: _____

Witness Type: PARTIAL

Date/Time Plugging Completed: 08/20/2012 1:00 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

A CIBP WAS SET AT 4080' AND CAPPED WITH 2 SKS OF CMT. THE CASING WAS RECOVERED FROM 2024' AND PULLED FROM THE WELLBORE. TUBING WAS RUN IN HOLE TO 1200', WHERE 50 SKS OF CMT WAS SPOTTED. TAGGED CMT AT 1280', SPOTTED 35 SKS OF CMT AT 744', PULLED TUBING TO 434' AND CIRCULATED TO SURFACE WITH 133 SKS OF CMT.

Top	Bot	Thru	Comments
4130	4147	CSG	


RECEIVED
KANSAS CORPORATION COMMISSION
SEP 04 2012
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CMTG 60/40 4% GEL

Plugged through: TBG

District: 02

Signed


9/10/12 (TECHNICIAN)