

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-007-22369-00-01
 Spot: NWSWNW Sec/Twnshp/Rge: 12-34S-10W
3661 feet from S Section Line, 5029 feet from E Section Line
 Lease Name: POLLOCK Well #: A1 'OWWO'
 County: BARBER Total Vertical Depth: 5067 feet

Operator License No.: 31191
 Op Name: R & B OIL & GAS, INC.
 Address: 912 N LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4547		WITH 2 SX CMT
CIBP		4840		
PC		387		CMT TO SURFACE
PROD	4.5	5067		WITH 225 SX CMT
SURF	8.625	261		WITH 166 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/22/2012 9:30 AM
 Plug Co. License No.: 30346 Plug Co. Name: SHAWNEE WELL SERVICE, INC.
 Proposal Rcvd. from: JEFF CAPPS Company: SHAWNEE WELL SERVICE, INC. Phone: (620) 254-7893

Proposed Plugging Method: SET CIBP @ 4540' & PUT 2 SX CMT ON TOP OF CIBP. RUN TBG IN TO 600' & FILL 4 1/2" CASING WITH CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 08/22/2012 10:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

4 1/2" CASING HAD PREVIOUSLY BEEN CIRCULATED TO SURFACE W/CMT THROUGH PORT COLLAR FROM 387 SET CIBP @ 4547' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. RUN TBG TO 600' & CIRCULATED CMT TO SURFACE WITH 69 SX CMT. PULLED TBG OUT & TOP OFF 4 1/2" CASING WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4926	4936		
4840			
4593	4624		

RECEIVED
 KANSAS CORPORATION COMMISSION
 SEP 04 2012
 CONSERVATION DIVISION
 WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
 AUG 30 2012
 KCC DODGE CITY

Signed Stephen J Pfeifer
 (TECHNICIAN)