

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-109-20,276-0000

LEASE NAME Jones

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 11 TWP. 11S RGE. 32W (E) or (W)

COUNTY Logan

Date Well Completed

Plugging Commenced 3-25-97

Plugging Completed 3-27-97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Coas. Div.
 office within 30 days.

4-22-97
 5-8

LEASE OPERATOR Thunderbird Drilling, Inc.

ADDRESS P. O. Box 97 Ellinwood, KS 67526

PHONE (316) 564-2577 OPERATORS LICENSE NO. 5131

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4660'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	288'	none
				4 1/2	4659'	1700'

RECEIVED
 KANSAS CORP. COM.
 APR - 11 AM '97

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s.
Plugged off bottom with sand to 3990' & ran 4 sks cement. Shot well at 2493', 2005', 1800', and 1700'. Came loose at 1700'. Allied pumped 100 sks cement w/350# hulls and displaced to 1700'. Pulled pipe to 300', pumped 65 sks cement w/150# hulls & circulated to surface. Pulled rest of pipe. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Thunderbird Drilling, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.


(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 3rd day of April, 19 97

Deane [Signature]
 Notary Public

My Commission Expires:



INC.

Guard Log

15-109-20276-0000

Marked

COMPANY ENERGY EXPLORATION, INC.
 15-109-20276 RECEIVED
 WELL NO. 2 ENEX JONES
 FIELD _____
 COUNTY ROGERS STATE KANSAS
 Location 1650 ESL-728 FEL NW/4 Other Services: NONE
 Sec. 11 Twp. 11 S Rge. 32 W

Permanent Datum: GROUND LEVEL Elev. 3040 Elev.: K.H. 3045
 Log Measured From: K.B. FINE Ft. Above Perm. Datum D.F. _____
 Drilling Measured From: KELOD BUSHING G.L. 3040

Date	2-7-88			
Run No.	ONE			
Depth - Driller	4660			
Depth - Logger	4657			
Btm. Log Inter.	4656			
Top Log Inter.	0			
Casing - Driller	858 @ 288			
Casing - Logger				
Bit Size	7.78			
Type Fluid in Hole	DRISCOSE M.O.			
Dens. @ 10' Vis.	9.6	40		
Fl. Loss	9.0	120 ml	ml	ml
Source of Sample	FLOLINE			
Rm @ Meas. Temp.	1.1	@ 40 F	@	F
Rm @ Meas. Temp.	8	@ 40 F	@	F
Rm @ Meas. Temp.	1.6	@ 40 F	@	F
Source Rm	Rm	CHARTS		
Rm @ BHT	36	@ 122 F	@	F
Time Since Circ.	1 1/2 HOURS			
Max. Rec. Temp	122	F		
Equip	Location	140	67.156	
Recorded By	J. BRUMB			
Witnessed By	C.W. NELSON			

FIELD PRINT

EQUIPMENT DATA

