

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-109-20009-00-00
LEASE NAME OAKLEY UNIT

WELL NUMBER 2-3

NOTICE: Fill out completely 810 Ft. from S Section Line
and return to Cons. Div. 4470 Ft. from E Section Line
office within 30 days

1-8-03

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 11 TWP. 11S RGE. 32W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY LOGAN
PHONE # (316) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 4/23/71

Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 12/10/02
Plugging Completed 12/10/02

The plugging proposal was approved on 12/10/02 (date)
By Witnessed and Approved by Darrel Dipman w/ KCC Hays, KS. (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? YES
Producing Formation LKC Depth to Top 4079 Bottom 4598OA TD 4662' PBTD 4612'
Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	283	8 5/8	283	0
		production	4660'	5 1/2	4660	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Ran open end tbg to 2424'. Pumped 115 sxs SMD cmt & 600#hulls down tbg. Pulled tbg to 1200'. Pumped 50 sxs cmt (same) & 100#hulls & circ cmt to sur. Hooked up to 5 1/2" csg. Pumped 20sxs cmt & SI @ 200# held Hooked onto 8 5/8" Pumped 20sxs cmt & SI @ 175# held. Well P/A. Witnessed and approved by Darrel Dipman w/KCC Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address 250 N. Water, Suite 300; Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK ss.
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this Dec 12 day of ,2002

Notary Public - Barbara J. Dodson [Signature]
My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



CR

SWIFT SERVICES, INC.

PO BOX 466

NESS CITY, 67560-0466

Invoice

DATE	INVOICE #
12/10/02	4942

BILL TO
Murfin Drilling Co. Inc. PO Box 277 Logan, KS 67646

RECEIVED
JAN 08 2003
KCO OPERATING

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Operator	Job Purpose
Net 30	2-3	Oakley	Logan	Co Tools	Oil	Abandoned	Wayne	PTA
PRICE REFERE...	DESCRIPTION				QTY	UNIT PRICE	AMOUNT	
575W	Milage				25	2.50	62.50T	
576W-P	Pump Charge				1	500.00	500.00T	
275	Cotton Seed Hulls				7	22.00	154.00T	
330	Swift Multi-Density				205	9.50	1,947.50T	
581W	Service Charge Cement				300	1.00	300.00T	
583W	Drayage				372.875	0.75	279.66T	
	Subtotal						3,243.66	
	Sales Tax					5.30%	171.91	
USED FOR <u>PIA 36</u>								
APPROVED <u>JT RK</u>								
Thank you for your business.						Total	\$3,415.57	



CHARGE TO:
MUAFEN DRILLING
 ADDRESS
 CITY, STATE, ZIP CODE

TICKET No 4942

PAGE 1 OF 1

12-10-02
 12:00 PM
 12-10-02

15/109-20009-0000

SERVICE LOCATIONS 1. NESS CITY, KS	WELL/PROJECT NO. 2-3	LEASE OAKLEY	COUNTY/PARISH LOGAN	STATE KS	CITY	DATE 12-10-02	OWNER SAFE
2.	TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR Co Tools	RIG NAME/NO.	SHIPPED VIA CT	DELIVERED TO LOGAN	ORDER NO.	
3.	WELL TYPE OIL	WELL CATEGORY ABANDONED	JOB PURPOSE PTA	WELL PERMIT NO.	WELL LOCATION OAKLEY - 1S, 14E, 2S		
4.	REFERRAL LOCATION	INVOICE INSTRUCTIONS					

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
575		1			MILEAGE # 103	25	ME			2.50	62.50
576		1			PUMP SERVICE	1	JOB			500.00	500.00
275		1			COTTON SEED HULLS	700	lbs	7	lbs	22.00	154.00
330		1			SWIFT MULTI-DENSITY STANDARD	205	lbs			9.50	1947.50
581		1			SERVICE CHARGE CRYST	300	lbs			1.00	300.00
583		1			DRYAGE	29830	lbs	372.875	TM	.75	279166

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X *[Signature]*
 DATE SIGNED **12-10-02** TIME SIGNED **0830** A.M. P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	3243
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?					
WE UNDERSTOOD AND MET YOUR NEEDS?					
OUR SERVICE WAS PERFORMED WITHOUT DELAY?					
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX	171
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL	3415
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND					57

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR
Wade Wilson

APPROVAL
 Thank You!

JOB LOG

SWIFT Services, Inc.

15109-20009-0000

DATE 12-10-02 PAGE NO. 1

CUSTOMER **MURFEE DRILLING** WELL NO. **2-3** LEASE **OAKLEY** JOB TYPE **PTA** TICKET NO. **4942**

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL/DAY)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	0800							ON LOCATION 8 5/8" = 283' 5 1/2" = 4660 2 3/8" x 5 1/2" PVR STOCK = 4200'
	0945	5	63.7	✓				1 ST PLUG - <u>115 SLS</u> CNT W/ <u>600" HULL</u> = 2430' (CIRCULATION TO POT = 22 SLS MOVED) PULL TUBING TO 1200'
	1040	5	27.7	✓				2 ND PLUG - CIRCULATED CNT WT TO SURFACE <u>50 SLS</u> = 1200' / <u>100" HULL</u> PULL TUBING OUT WELL - RTG UP TO 5 1/2" CASING
	1124	2	11	✓		200		TOP OFF WELL <u>20 SLS</u> S/E = 200 PSW
	1140	2	11	✓		175		PUMP DOWN BEANS HEAD <u>20 SLS</u> S/E = 175 PSW WASH UP
	1230							JOB COMPLETE THANK YOU WAVE DUST