

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15051-194620000
API NUMBER 4-23-62

LEASE NAME Gustus

WELL NUMBER 7

SPOT LOCATION SE $\frac{1}{4}$

SEC. 9 TWP. 11 RGE. 19 (E) (W)

COUNTY Ellis

Date Well Completed 4-23-62

Plugging Commenced 5-15-90

Plugging Completed 5-15-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS Box 723 Hays, Kansas 67601

PHONE # (913) 628 6101 OPERATORS LICENSE NO. 5245

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ if not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3593

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	177	8 5/8		None
	Casing	0	3590	5 $\frac{1}{2}$		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Perf 2 holes 1375' Run tubing to 2500 Spot 75 sks 65/35 pos with 8% gel with 250# hulls. Pull tubing to 1400' mix 150 sks 65/35 pos with 8% gel. Circulate cement to surface. Hook up to surface and mix and pump 25 sks 65/35 8% gel 400# max. SIP 200#. Hook to 5 $\frac{1}{2}$ casing Mix 100 sks 65/35 pos 8% gel 200# hulls. Max. press. 800# SIP 700#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245
Address Box 723 Hays, Kansas 67601

BJ Services cementer

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Kansas

ROSEMARY SMITH
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXP. MAY 1, 1991

SUBSCRIBED AND SWORN TO before me this 16 day of May, 1990

Rosemary Smith
Notary Public

My Commission expires: 5-1-1991