

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-02256-0000
LEASE NAME Falconberry "A"
WELL NUMBER #1
SPOT LOCATION SW SE NW
SEC. 10 TWP. 11 RGE. 19 (X or (W))
COUNTY Ellis
Date Well Completed 3/10/54
Plugging Commenced 3/13/86
Plugging Completed 3/14/86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Okmar Oil Company
ADDRESS 970 Fourth Financial Center, Wichita
PHONE # (316) 265-3311 OPERATORS LICENSE NO. 5245

Character of Well OIL
(Oil, Gas, D&A, SHD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? District #6, Hays

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation LKC, Arbuckle Depth to top 3300', 3613' bottom 3534, 3617. D. 3617'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Oil	3334	3338	8 5/8"	227'	None
Arbuckle	Oil	3613	3617	5 1/2"	3614'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Ran tbq open ended to 3567'. Spotted continuous column of cement from 3567' to surface. Used total of 185 sx of BJ-Econolite cement (yield-3 ft³/sx). Pumped 15 sx in 5 1/2"-8-5/8" annulus.


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245
Address 970 Fourth Financial Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Evan C. Mayhew (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Evan C. Mayhew
(Address) 970 Fourth Financial Center



SUBSCRIBED AND SWORN TO before me this 22 day of May, 1986

Cecelia A. Bowser
Notary Public

My Commission expires: August 5, 1987

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1986
CONSERVATION DIVISION
Wichita, Kansas

Trans Era Petroleum, Inc.
Falconberry "A" #1

SW SE NW 10-11-19
Ellis County, Kans.

Total Depth: 3617'
Comm. 2/25/54
Comp. 3/10/54

Casing

3 5/8" Set @ 227'
5 1/2" Set @ 3614'

Cement

200 ex. Portland
125 ex. Lehigh

Formation

Depth

Surface formation-shale	100
Shale-shells	180
Sand	195
Shale	250
Shale-sand	1150
Shale-red bed	1300
Sand	1334
Sand-red bed	1434
Anhydrite	1466
Red bed-shale	1650
Shale-lime	1920
Shale-shells-lime	2075
Shale-lime	3276
Lime	3513
Lime-conglomerate	3562
Conglomerate	3604
Shale	3617'


STATE OF KANSAS }
 } ss
RUSSELL COUNTY }

I hereby certify that the above information is true and correct
to the best of my knowledge,

Car Betz

Subscribed and sworn to before me this 16th day of March, 1954.

Margie Cooper
Notary Public



My commission expires: 1-30-57.

STATE COMMISSION

MAY 2

CONSERVATION