

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-0510225 2-0000  
API NUMBER None Assigned

LEASE NAME Albert

WELL NUMBER #2

SPOT LOCATION NW SW SW

SEC. 10 TWP 11S RGE. 19 (X) or (H)

COUNTY Ellis

Date Well Completed 11/22/52

Plugging Commenced 7/1/87

Plugging Completed 7/1/87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS 970 Fourth Financial Center

PHONE # (316) 265-3311 OPERATORS LICENSE NO. 5245

Character of Well Oil  
(Oil, Gas, D&A, SHD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays Office

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation Arbuckle Depth to top 3560' bottom 3565' T.D. 3565'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	139	None
				5 1/2"	3564	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. All cement plugs spotted thru tbg.

45 sx econolite cmt @ 3000'  
60 sx econolite cmt @ 1000' (circ cmt to surface)  
Tied on to 5 1/2" csg & pumped 100 sx econolite cmt down csg - pressured to 200# @ end of job.  
Pumped 5 sx econolite cmt down 5 1/2 x 8 5/8" annulus, pressured to 300#.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245

Address 970 Fourth Financial Center

Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Evan C. Mayhew (employee of operator) or (operator) of above-described well; being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

AUG 3 1987


(Signature) Evan C. Mayhew

(Address) 970 4th Financial Center

SUBSCRIBED AND SWORN TO before me this 29th day of July, 1987

Kathryn A. Dought  
Notary Public

My Commission expires: 6-13-89



Company: Okmar Oil Company Farm: Albert Sessin #2  
 Contractor: Glenn R. Nye Drilling Company Location: NW SW SW 10-11-19  
 Commenced: December 3, 1952 Ellis County, Kansas  
 Completed: December 14, 1952 Casing Record: 8 5/8" set at 139'  
 5 1/2" set at 3564'

(figures indicate bottoms)

shale & sand	60	
shale & sand	65	
blue shale	139	
shale	530	
sand & shale	925	
shale & sand	1025	
shale & red bed	1350	
anhydrite	1390	
shale	1400	
shale & red bed	1765	
shale & shells	1865	
shale & lime	1965	
lime & shale	2120	
lime & shale	2220	
lime & shale	2300	
lime & shale	2365	
lime & shale	2565	
lime & shale	2640	
shale & lime	2735	
lime & shale	2920	
lime & shale	3025	
lime & shale	3101	
lime & shale	3142	
lime & shale	3195	
lime & shale	3240	Top Heebner 3205'
lime & shale	3285	Top K.C. 3245'
lime	3316	
lime	3364	
lime	3413	
lime	3455	
lime	3488	
lime & shale	3551	Cong. 3482'
simpson	3560	
T.D.	3564	Top Arbuckle 3564'


I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

GLENN R. NYE DRILLING COMPANY

By Claude N. Bard

STATE OF KANSAS )  
 ) SS  
 ELLIS COUNTY )

Subscribed to and sworn to before me, a notary public, in and for said County and State this 16th day of Jan., 1953.



John L. Spiss  
 NOTARY PUBLIC

My Commission Expires May 9, 1953