

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15-051-23,367-0001
LEASE NAME Allison
WELL NUMBER 3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4190 Ft. from S Section Line
3960 Ft. from E Section Line
SEC. 13 TWP. 11 RGE. 19 W
COUNTY Ellis
Date Well Completed 2-19-83
Plugging Commenced 1-31-97
Plugging Completed 1-31-97

LEASE OPERATOR Manta Petroleum, Inc.
ADDRESS P.O. Box 4491
PHONE# (303) 892-8860 OPERATORS LICENSE NO. 31638

Character of Well Input
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)
by _____ (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____
Producing Formation LKC 'K' Depth to Top 3406' Bottom 3416' T.D. 3448'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put in	Pulled out
<u>LKC 'K'</u>	<u>Oil</u>	<u>3406</u>	<u>3416</u>	<u>8-5/8"</u>	<u>293'</u>	<u>0'</u>
				<u>4-1/2"</u>	<u>3535'</u>	<u>0'</u>

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Pump 275 sx. 60/40 posmix w/ 10% gel (tbg. @ 1375') followed by 500# hulls. Circulate cement, POH w/ tbg., pumped remainder of job & pressure up to 600 #. Tie on to backside, pressure up to 600#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. N/A

Address P.O. Box 31; Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Manta Petroleum, Inc.

STATE OF Colorado COUNTY OF ARAPAHOE, ss.

Steve Beckley (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) P.O. Box 4491; Englewood, CO 80155

SUBSCRIBED AND SWORN TO before me this 16th day of MAY, 1997.

[Signature]
Notary Public

My Commission Expires: 2-17-99