

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-051-05083-0000

API NUMBER 2-9-55  
 LEASE NAME Gustus  
 WELL NUMBER 2

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

       Ft. from S Section Line  
SE SE NE Ft. from E Section Li  
 SEC. 16 TWP. 11 RGE. 19 (E) or (W)  
 COUNTY Ellis  
 Date Well Completed 2-9-55  
 Plugging Commenced 2-26-92  
 Plugging Completed 2-26-92

LEASE OPERATOR Berexco, Inc.  
 ADDRESS Box 723 Hays, Kansas 67601  
 PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5363

Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-26-92 (date)  
 by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed?        If not, is well log attached?         
 Producing Formation        Depth to Top        Bottom T.D. 3501

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	1280	8 5/8		None
	Casing	0	3400	5 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from        feet to        feet each set.  
Hook up BJ Services. Pump down tubing 20 bbl. NT 4 BPM 500# getting blow on 5 1/2 casing and 8 5/8 casing. Mixed 235 sk. cement circulate on 5 1/2 and 8 5/8. Stop mixing back off tubing with tongs backed off. Pulled 42 jts. and 8' sub. Hook up to 5 1/2 mix 30 sk. circulate on 8 5/8 - close in 8 5/8. Pressure up 5 1/2 to 500 PSI. Mixed total 265 sk. 60/40 pos. 8% cal.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Berexco, Inc. License No. 5363  
 Address Box 723 Hays, Kansas 67601  
 RECEIVED  
 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc. LIAR - 4 1992  
 STATE OF Kansas COUNTY OF Ellis, ss. CONSERVATION DIVISION  
 Wichita, Kansas

Mr. Ted Crawford (Employee of Operator) or (Operator)  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

NOTARY PUBLIC - State of Kansas  
 ROSEMARY SMITH  
 My Appt. Exp. 5-1-1995

(Signature) Ted Crawford  
 (Address) Box 723 Hays, Mo 67601  
 SUBSCRIBED AND SWORN TO before me this 2 day of March, 19 92  
Rosemary Smith  
 Notary Public

My Commission Expires: 5-1-1995