

LEASE NAME Simmons  
 WELL NUMBER 4  
 SPOT LOCATION SE SW SW  
 SEC. 16 TWP. 11 RGE. 19 (E) of 14  
 COUNTY Ellis  
 Date Well Completed 5/1965  
 Plugging Commenced 5-29-90  
 Plugging Completed 5-29-90

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Okmar Oil Company  
 ADDRESS Box 723 Hays, Kansas 67601  
 PHONE # (913) 628 6101 OPERATORS LICENSE NO. 5245

Character of Well Oil  
 (Oil, Gas, D&A, S&D, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes  
 Which KCC/KDHE Joint Office did you notify? Hays, Kansas 67601  
 Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3495  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	176	8 5/8		None
	Casing	0	3492	5 1/2		None


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Run tubing to 3400'. Mix ans spot 100 sks. 65/35 pos, 8% gel, and 200# hulls. Pull tubing up to 1300' Mix 130 sks 65/35 pos, 8% gel, 200# hulls. Cement circulated to top. Pull tubing. Hook up to annulus. Pressured to 500# OK. Hook up to 5 1/2 mix and squeeze in 120 sks. 65/35 pos, 8% gel, 100# hulls at 800# 800#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245  
 Address Box 723 Hays, Kansas 67601  
BJ Services (cementer)

STATE OF Kansas COUNTY OF ELLIS, ss.  
Mr. Ted Crawford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford  
 (Address) Box 723 Hays, Ks 67601  
 SUBSCRIBED AND SWORN TO before me this 8 day of June, 1990  
Rosemary Smith  
 Notary Public



My Commission expires: 5-1-1991