

STATE CORPORATION COMMISSION
130, S. Market, Room 2078
Wichita, KS 67202

15-051 22382 00-00
LEASE NAME

4/10/64
Wiles

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 3
2310 Ft. from S Section Line
2310 NW NW SE Ft. from E Section Line

LEASE OPERATOR Berexco, Inc.
ADDRESS Box 723
PHONE (785) 628 6101 OPERATORS LICENSE NO. 5363

SEC. 16 TWP. 11 RGE. 19 (E) or (W)
COUNTY Ellis
Date Well Completed 4/10/64
Plugging Commenced 3/27/2001
Plugging Completed 3/27/2001

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/27/2001 (date)
by Pat Staab (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3503

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	175	8 5/8		
	Production	0	3502	. 5 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each section.
Mix 165 sk. 60/40 pos with 10% gel with 600# hulls. Circulate cement to surface. Pull tubing. Hook to 5 1/2 casing. top off with 20 sk. cement. Pressure to 500#. Shut in 300# Hook to 8 5/8 mix 5 sk. pressure 500#. Use 190 sk. 60/40 pos with 10% gel and 600# hulls Well plugged.

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Curtis Gabel (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) C. Gabel

(Address) Box 723 Hays, Mo. 67601

SUBSCRIBED AND SWORN TO before me this 3 day of April, 2001

NOTARY PUBLIC - STATE OF KANSAS
ROSEMARY SMITH
My Commission Expires 5/10/2001

Rosemary Smith
Notary Public
5/10/2001

OK