


WELL PLUGGING RECORD
AND REC

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Ellis County, Sec. 30 Twp. 11 Rge. 19 (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines _____
Lease Owner Osage Oil and Gas
Lease Name Zerfas Well No. 1
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6-11-57 _____ 19____
Plugging completed 6-19-57 _____ 19____
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand 3500 feet. Dumped 4 sacks cement. Pulled pipe to 1200 feet. Circulated 25 sacks jell mud. Pulled pipe to 600 ft. Pumped 50 sacks cement down pipe. Pulled pipe. Bailed hole down 35 feet. Set rock bridge dumped 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E & L Casing Pulling Co.
Address 1416 Coolidge, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. D. F. MOORE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
302 Petroleum Building, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of September, 19 57

My commission expires NORMA J. JOHNSON, Notary Public
Commission Expires Aug. 2, 1958

PLUGGING
FILE SEC 30 T 11 R 19W
BOOK PAGE 19 LINE 40

09-24-57

ROTARY DRILLING LOG

OPERATOR: Osage Oil & Gas Co., Inc.
 ZERFAS NO. 1
 SW NE SE Sec. 30-11-19W,
 Ellis County, Kansas

CONTRACTOR: Prime Drilling Company
 COMM: 5/19/57
 COMP: 6/2/57

Formations:

Surface Clay & Sand	90'
Shale & Shells	675'
Sand & Shale	775'
Shale & Shells	1025'
Sand	1215'
Shale & Shells	1480'
Anhydrite	1520'
Shale & Shells	2120'
Shale & Lime	3255'
Lime	3345'
Lime & Shale	3995'
Lime	3610'
Lime & Shale	3665'
Lime Shale & Chert	3698'
Cherty Lime & Shale	3735'
Shale & Lime	3775'
Rotary Total Depth	3775'

Remarks: Set 8-5/8" surface casing
 at 246' cemented with 160 sacks common
 cement, 3 sacks C.C.

Set 5-1/2" Casing at 3774' cemented
 with 100 sacks common cement.

We certify the above log is true and
 correct to the best of our knowledge
 and belief.

PRIME DRILLING COMPANY

R.R. McNicol

R. R. McNicol

RECEIVED
 STATE OF KANSAS

87
 CONS

PLUGGING
 FILE SEC 30 T 11 R 19W
 BOOK PAGE 19 L 40