

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 35 Twp. 11 Rge. 19 (E) (W)

Location as "NE/CNWKSWK" or footage from lines S/2 SE NW
Lease Owner Woodman - Iannitti Oil Company
Lease Name Vine Well No. 1
Office Address P. O. Box 387 Hoisington, Kansas 67544
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 12-19-69 19
Plugging completed 12-27-69 19
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation Depth to top Bottom Total Depth of Well 3680 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	194	None
				5 1/2	None	2977
RECEIVED STATE CORPORATION COMMISSION JAN 6 1970 CONSERVATION DIVISION WICHITA, KANSAS						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in unit. Put up pole and started digging cellar.

Finished digging cellar. Plugged bottom back to 3500' with sand. Dumped 5 sacks of cement on bottom with dump bailer.

Had collar welded on 5 1/2" casing and strapped. Checked hole with bailer and rigged up jacks. Worked pipe from 10" stretch to 24" stretch at 2500 psi or 110,000 lbs.

Shot pipe at 3001' - took 2 1/2 hours to get shot down. Worked pipe loose. Pulled 30 joints of 5 1/2" casing.

Pulled 48 joints of pipe. Tore down jacks and loaded out trailer.

Tallied pipe. Sun Cementing Company plugged hole with 20 sacks of gel - 5 sacks of hulls and 90 sacks of 50/50 pozmix cement blended with 6%. Let down pole, finished loading out rig and moved off location.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

James W. Rockhold

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

James W. Rockhold
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 31 day of December, 1969

My commission expires May 27, 1973

Notary Public.



K. T. WOODMAN
RES. PHONE AM 5-3572
OFFICE PH. AM 5-7650
WICHITA, KANSAS

D. J. IANNITTI
TELEPHONE 653-2381
HOISINGTON, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors
706 UNION NATIONAL BUILDING
WICHITA, KANSAS 67202

Company: Woodman & Iannitti Drilling Co.
Lease: Vine No. 1
Location: SW SE NW
Section: 35-11-19
County: Ellis
Comm: March 19, 1969
Compl: March 27, 1969
Total Depth: 3680'
Casing: 8 5/8 @ 194' w/130 sx
5 1/2 @ 3679 1/2 w/100 sx

Figures Indicate Bottom Of Formations:

50	Clay & Shale
160	Rock & Shale
195	Shale
730	Shale
941	Shale & Streaks Of Sand
1100	Sand
1460	Red Bed
1480	Anhy
1503	Anhy
1900	Shale & Shells
2105	Lime
2330	Lime
2485	Lime
2610	Lime
2780	Lime
2940	Lime
3040	Lime
3266	Lime
3330	Lime
3386	Lime
3450	Lime
3525	Lime
3582	Lime
3630	Lime
3680	Lime

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1969
CONSERVATION DIVISION
Wichita, Kansas

I certify the above to be a true and correct copy of the driller's log and the geological tops to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

K. T. Woodman
K. T. Woodman